


THE DAVID ADAMANY
UGL – UNDERGRADUATE LIBRARY
BUILDING #096
FIRST FLOOR



DISCLAIMER:
WAYNE STATE UNIVERSITY, FACILITIES PLANNING AND MANAGEMENT
MAKES THESE DOCUMENTS AVAILABLE ON AN "AS IS" BASIS.
THESE DRAWINGS WERE CREATED USING AUTOCAD FROM AUTODESK AND
ARE ACCURATE FOR SPACE MANAGEMENT, "FLOOR PLAN" USE. THE
USERS WILL HOLD HARMLESS WSU, ITS OFFICERS, AGENTS, AND
EMPLOYEES FROM DAMAGES OR COST, INCLUDING REASONABLE
ATTORNEY'S FEES, ARISING FROM THE USE OF THESE DRAWINGS.



Electrical Legend

- E 1 –Install conduit/Raceway back box for data drops (Each D indicated in the drawing) with exception of CAM's and WAP's.
 - Relocate(1) light switch near the new door
 - Furniture whip to be supplied by vendor, electricians will hard wire the furniture.
 - E 2 –Install conduit/Raceway back box for data drops (Each D indicated in the drawing) with exception of CAM's and WAP's.
 - (1) Duplex receptacles & 1 Data conduit for TV/behind TV location.
 - Relocate 4 light fixtures
 - Rewire & Provide (2) light switches near the doors in workshop area.
 - Install(2) duplex power on 3 new walls.
 - 2 cores and install with salvaged floor boxes
 - E 3 –Rewire/Relocate light fixture per room provide light sensor switch in all 3 rooms
 - Conduit for data drops
 - provide 1 duplex next to data drop.
 - E 4 – Install 1 duplex behind TV receptacle
 - E 5 – 4 floor cores and install salvaged floor box
 - 2 TV mobile carts/ 2 in open area.
 - 1 floor core centre of table
 - install salvaged floor box
 - E 6 – Remove/relocate/demo existing Light Fixt.
 - furnish /install new light fixtures in 5 rms
 - rework/provide switch/light fixtures in 2 rms
 - install WSU provided light fixtures (6) in 2 rms.
 - Provide/relocate light sensor switch in 10 rms
 - 1 duplex and 1 quad receptacles per room
 - add conduit for data drop in each room
 - demo 9 floor boxes in new office rooms.
 - E 7 – Install 2 quad plugs for lockers/ vending
- Alternate cost:
 FA– Add 1 Horn strobe in Workshop room.
 FA– Add 1 Horn strobe in conference room.

FLOOR PLAN

SCALE: 1/32" = 1'-0"



DRAWING TITLE
UGL CAREER
SERVICES
PROPOSED PLAN

FIRST FLOOR

GENERAL NOTES
DISCLAIMER: WAYNE STATE UNIVERSITY,
FACILITIES PLANNING AND MANAGEMENT
MAKES THESE DOCUMENTS AVAILABLE
ON AN "AS IS" BASIS. THESE
DOCUMENTS WERE CREATED USING
AUTOCAD FROM AUTODESK AND ARE
ACCURATE FOR SPACE MANAGEMENT,
"FLOOR PLAN" USE. THE USERS WILL
HOLD HARMLESS WSU, ITS OFFICERS,
AGENTS, AND EMPLOYEES FROM
DAMAGES OR COST, INCLUDING
REASONABLE ATTORNEY'S FEES,
ARISING FROM THE USE OF THESE
DRAWINGS. DO NOT TREAT THESE
DOCUMENTS AS ACCURATE. IT IS
EXPECTED THAT CONTRACTORS WILL
CONDUCT FIELD VISITS FOR
OBSERVATION AND MEASUREMENTS.

NO.	FOR	DATE
1	FOR BIDDING	12/19/2024
2	Addendum	01/9/2025

FIRM NAME AND ADDRESS
WAYNE STATE UNIVERSITY
FACILITIES PLANNING AND MANAGEMENT
DESIGN & CONSTRUCTION SERVICES
5454 CASS AVENUE
DETROIT, MI 48202

PROJECT NAME AND ADDRESS
UGL CAREER SERVICES
5155 GULLEN MALL,
DETROIT, MI 48202

PROJECT NUMBER	SHEET
096-414946	1
DATE	
10/11/2024	